



CENTRAL UNIVERSITY OF HARYANA

(Established vide Act No. 25 (2009) of Parliament)

Jant-Pali, Mahendergarh-123029

NOTICE INVITING QUOTATION NO. 05/2023

Sealed item rate quotations are invited on behalf of Central University of Haryana, Mahendergarh. The quotation should reach the office of the Executive Engineer, Room No.-218, Administrative Building, CUH on or before 24/02/2023 upto 2:00 PM. The quotation shall be opened on the next working day i.e. 27/02/2023 at 11:00 AM. The bidders may attend the said meeting on 27/02/2023.

Name of Work: Partition work in visitor's room of Vice-Chancellor's Office and Dr. Ambedkar Centre of Excellence.

Sr. No.	Description	Qty.	Unit	Rate	Amount
1	Providing & fixing wooden partition including well seasonal pine/hillock wood members of minimum size 50x50 mm in frames, 12 mm thick ply on both sides including pasting of 1 mm thick laminates including all labour, taxes, carriage etc. Nothing extra will be paid. The work will be carried out as per direction of Engineer-In-Charge.	16	Sqm.		
2	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately): For fixed portion Powder coated aluminium (minimum thickness of powder coating 50 micron)	130	Kg		

R. Kumar
17/02/23

3	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer in-charge. Pre-laminated particle board with decorative lamination on both sides.	30	Sqm.		
Total					

Terms and Conditions:

1. The work will be carried out as per the satisfaction of the engineer in charge.
2. GST registration certificate of the agency is required to be enclosed along with quotation.
3. Validity of the quotations will be 60 days from the date of opening.
4. The rate includes all taxes like GST, and other taxes and carriage of the material etc.
5. Time of completion of work will be 20 days.
6. No advance payment will be made.
7. Conditional quotations will not be considered.
8. The agency should inspect the site before quoting the rate.
9. The quantity of items in BOQ is tentative which may change depending upon site conditions.
10. The CUH will not be responsible for any accident. The agency should provide proper safety tools to its workers.
11. Time is the main essence of the contract. Hence, an appropriate penalty upto 10% maximum can be imposed on the agency for delayed completion of work.
12. No labor below the age of 18 years be employed on site.
13. All T&P required will be arranged by the contractor.
14. The agency/Contractor shall make its own arrangement of water & electricity.
15. Security deposit @5% shall be recovered from the bill of the bidder.


17.02.22

Executive Engineer (Infra.)